



ଚୌଦ୍ୱାର ପୌରପରିଷଦ କାର୍ଯ୍ୟାଳୟ, ଚୌଦ୍ୱାର

OFFICE OF THE MUNICIPAL COUNCIL, CHOUDWAR
Govt. of Odisha (H&U.D Deptt) CUTTACK (ODISHA) PIN-754071
Phone No- 0671-2394272(0) e-mail: choudwarmunicipality@gmail.com



No. Dev. 1489

Date. 06/12 / 2025

Quotation Call Notice

Sealed quotations are invited from the intending Authorized Firms/ Suppliers/Dealers & Agencies having up to date GST Registration copy, PAN card copy and valid registration copy for **Supplying of GFRC Jali (Boundary Wall), GFRP Cladding M.S Railing complete, S.S Railing Complete, Design Stone Railing in different places under Choudwar Municipality** as per detailed description of different items & specifications as mentioned in the official website of Choudwar Municipality-www.choudwarmunicipality.in

| Sl. No | Description |
|--------|--|
| 1 | Supplying of GFRC Jali (Boundary Wall), GFRP Cladding M.S Railing complete, S.S Railing Complete, Design Stone Railing in different places under Choudwar Municipality |

The prescribed quotation schedule can be obtained from the office of the Choudwar Municipality, Choudwar during office hours on all working days from dt.08.12.2025 to dt.26.12.2025 within 1.00 PM on payment of Rs.10000/- (Rupees Ten Thousand) only in the shape of Cash/Demand Draft in favour of the Executive Officer Choudwar Municipality towards the paper cost which is non-refundable. The Quotation paper will be received upto 1.00 PM by this office within dt.26.12.2025 through Regd post/Speed post or in person and the same will be opened on the same date at 3.00 PM in the office of Choudwar Municipality in the presence of the quotationer or their authorised representative who wishes to remain present. The quotation delay in postal delivery after due date and time will not be taken into consideration.

The authority reserves right to reject any or all quotations without assigning any reason thereof.

Sd/-

Executive Officer
Choudwar Municipality

Memo No. Dev/ 1490 /Date. 06 / 12 /2025

Copy to Office Notice Board/www.choudwarmunicipality.in for wide publication.

Sd/-

Executive Officer
Choudwar Municipality

Memo No. Dev/ 1491 /Date. 06 / 12 /2025

Copy submitted to the Collector & District Magistrate, Cuttack/Project Director, DUDA, Cuttack for kind information.

Sd/-

Executive Officer
Choudwar Municipality

Memo No. Dev/ 1492 /Date. 06 / 12 /2025

Copy submitted to the Director, I&PR Dept. Govt. of Odisha with request to publish the matter in one Odia Daily & one English Daily preferably Sambad & Times of India newspapers for one time with minimum size and supply bills in duplicate for payment.

Sd/-

Executive Officer
Choudwar Municipality



ଚୌଦ୍ୱାର ପୌରପରିଷଦ କାର୍ଯ୍ୟାଳୟ, ଚୌଦ୍ୱାର
OFFICE OF THE MUNICIPAL COUNCIL, CHOUDWAR
Govt. of Odisha (H&U.D Deptt) CUTTACK (ODISHA) PIN-754071
Phone No- 0671-2394272(O) e-mail: choudwarmunicipality@gmail.com



Submission of Quoted rate for Supplying of GFRC Jali (Boundary Wall), GFRP Cladding M.S Railing complete, S.S Railing Complete, Design Stone Railing in different places under Choudwar Municipality
Vide Quotation Call Notice No. Dev/....., dtd,

| Sl No | Description of Items | Unit | Rate quoted without GST | Rate quoted with GST |
|-------|---|-------|-------------------------|----------------------|
| 1 | Supplying, Providing, and fixing GFRC (Glass Fibre Reinforced Concrete) Jali Panels of approved design, pattern, thickness (typically 20–35 mm) and size, including transporting and handling the panels with care; preparing the boundary wall surface and installing necessary MS framing/supports for fixing; securely anchoring the GFRC panels to the frame/wall using stainless-steel brackets, anchor bolts or fasteners as specified; cutting, trimming and shaping the panels neatly to fit corners, edges and architectural details; grouting around joints and fixing points with non-shrink grout to ensure stability and seamless appearance; applying touch-up, polishing or surface finishing as required; and completing the work in every respect as per approved drawings, manufacturer's recommendations and the direction of the Engineer-in-Charge. | 1 sqm | | |
| 2 | Supplying Providing and fixing GFRP (Glass Fibre Reinforced Polymer) Cladding Panels of approved design, thickness (typically 4–8 mm) and size, including thorough surface preparation by cleaning, levelling and applying primer/bonding coat where required; fixing the panels using polymer-modified adhesive and stainless-steel mechanical fasteners/anchor bolts as specified; ensuring proper alignment, level and spacing with uniform joints; cutting and shaping the panels accurately for edges, corners, openings and architectural details; sealing all joints with weather-resistant sealant/epoxy grout to ensure a neat, watertight and durable finish; applying necessary touch-up or protective coating as recommended by the manufacturer; and completing the work in all respects as per approved drawings, specifications and the direction of the Engineer-in-Charge. | 1 sqm | | |
| 3 | Supplying Providing, fabricating and fixing MS Railing complete, using IS-standard mild steel sections such as MS pipes, flats, angles or square/rectangular tubes of approved size and design, including precise cutting, bending, welding and grinding to achieve smooth joints and accurate geometry as per approved drawings; assembling and erecting the railing in position; anchoring the railing securely to RCC/brick/steel base using base plates, anchor bolts, grouting or welding as required; applying one coat of anti-corrosive primer and two coats of weather-resistant enamel paint of approved shade; finishing all exposed surfaces neatly with smooth edges; ensuring proper line, level, verticality and rigidity of railing; and completing the work with all materials, labour, tools and accessories as directed by the Engineer-in-Charge. | Kg | | |
| 4 | Supplying Providing and fixing SS Railing complete using SS 304 grade pipes/sections of approved diameter, thickness and design, including accurate cutting, bending and TIG welding; grinding, buffing and mirror/matte polishing of all joints and exposed surfaces to achieve a seamless finish; fixing the railing in position using stainless steel base plates, brackets, anchor bolts and necessary fittings; securely anchoring the railing to RCC/brick/steel base with proper alignment, level and verticality; providing all accessories such as end caps, elbows, connectors and decorative elements as required; ensuring smooth edges and high-quality workmanship; cleaning the railing after installation; and completing the work in all respects with all materials, tools and labour as per approved design and the direction of the Engineer-in-Charge. | Kg | | |
| 5 | Supplying Providing and installing Design Stone Railing using carved natural stone members of approved type, colour and thickness, including cutting, dressing and machine/manual carving as per the approved architectural pattern; polishing all exposed surfaces to the required finish; assembling balusters, handrails, base blocks and corner pieces accurately using cement mortar or stainless-steel dowels/anchors for secure fixing; preparing the base by levelling and grouting; erecting the railing in correct line, level and alignment; filling joints with matching pigment mortar or epoxy where required; performing final cleaning and finishing for a uniform appearance; and completing the work in every respect with all materials, tools, equipment and labour as directed by the Engineer-in-Charge. | Sqm | | |

Signature of Quotationer

Date:

Executive Officer
Choudwar Municipality